

SECTION 07211 – BATT INSULATION

1. GENERAL:

- A. THE CONTRACTOR SHALL FURNISH ALL LABOR, MATERIALS, TOOLS, EQUIPMENT, AND PERFORM ALL WORK AND SERVICES FOR THE INSTALLATION OF ALL BATT INSULATION, AS SHOWN ON DRAWINGS AND AS HEREIN SPECIFIED IN ACCORDANCE WITH PROVISIONS OF THE CONTACT DOCUMENTS.
- B. ALTHOUGH SUCH WORK IS NOT SPECIFICALLY INDICATED, FURNISH AND INSTALL ALL SUPPLEMENTARY OR MISCELLANEOUS ITEMS, APPURTENANCES AND DEVICES INCIDENTAL TO OR NECESSARY FOR A SOUND, SECURE AND COMPLETE INSTALLATION.

2. PRODUCT DELIVERY, STORAGE AND HANDLING:

- A. MATERIALS DELIVERED TO THE PROJECT SITE SHALL BE IN MANUFACTURER'S ORIGINAL UNOPENED PACKAGING. STORAGE AT SITE SHALL BE PROTECTED AGAINST ANY DAMAGES. DELIVER SO THAT STOCKS OF MATERIALS ON THE PROJECT WILL PERMIT UNINTERRUPTED PROGRESS OF WORK.

3. MATERIALS:

- A. THE CONTRACTOR SHALL INSTALL 6" FIBERGLASS BATT INSULATION OVER LAY-IN CEILINGS OVER MUSIC DEPARTMENT CLASSROOMS, PRACTICE ROOMS, TEACHER PLANNING ROOMS AND ALL OTHER ROOMS IN MUSIC DEPARTMENT AND ALL OTHER AREAS WHERE SHOWN ON DRAWING.
- B. THE CONTRACTOR SHALL INSTALL 6" FIBERGLASS BATT INSULATION OVER LAY-IN CEILINGS OF TEACHER PLANNING ROOMS, TEACHER RESTROOMS AND ALL OTHER ROOMS WHERE SHOWN ON DRAWING.
- C. THE CONTRACTOR SHALL INSTALL 4" FIBERGLASS BATT INSULATION IN THE DEMISING WALLS BETWEEN CLASSROOMS AND WHERE OTHERWISE INDICATED ON THE DRAWINGS. BATT INSULATION SHALL BE PINNED IN PLACE IF GYPSUM BOARD IS NOT INDICATED ON BOTH SIDES OF THE WALL. INSULATION SHALL BE STUFFED BETWEEN THE TOP TRACK OF THE SOUND WALLS AND THE DECK.
- D. ALL MATERIALS SHALL BE INSTALLED IN COMPLETE ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS THESE SPECIFICATIONS ARE MORE STRINGENT.

4. PROTECTION:

TAKE PRECAUTIONS TO PROTECT ALL INSULATION, BOTH DURING AND AFTER INSTALLATION, FROM DAMAGE OF ANY KIND.

END OF SECTION