

SECTION 10522 – FIRE EXTINGUISHERS AND CABINETS

1. GENERAL:

- A. THE CONTRACTOR SHALL FURNISH ALL LABOR, EQUIPMENT AND PERFORM ALL WORK AND SERVICES FOR THE INSTALLATION OF FIRE EXTINGUISHERS AND CABINETS AS SHOWN ON THE PLANS, AS HEREIN SPECIFIED, IN ACCORDANCE WITH PROVISIONS OF THE CONTRACT DOCUMENTS.
- B. ALTHOUGH SUCH WORK IS NOT SPECIFICALLY INDICATED, FURNISH AND INSTALL ALL SUPPLEMENTARY OR MISCELLANEOUS ITEMS, APPURTENANCES AND DEVICES INCIDENTAL TO OR NECESSARY FOR A SOUND, SECURE AND COMPLETE INSTALLATION.

2. DELIVERY AND STORAGE:

MATERIALS DELIVERED TO THE PROJECT SITE SHALL BE IN MANUFACTURER'S ORIGINAL UNOPENED PACKAGING. STORAGE AT SITE SHALL BE PROTECTED AGAINST ANY DAMAGES. DELIVER SO THAT STOCKS OF MATERIALS ON THE PROJECT WILL PERMIT UNINTERRUPTED PROGRESS OF WORK.

3. MATERIALS:

- A. FURNISH FIRE EXTINGUISHERS AND CABINETS WITH EXTINGUISHERS WHERE INDICATED.
  - 1. EXTINGUISHERS: COSMIC 10E, 4A-80BC WITH BRACKET BY J.L. INDUSTRIES
  - 2. CABINETS: AMBADOR 1017-F10 BY J.L. INDUSTRIES

4. INSTALLATION:

- A. EXTINGUISHER TO BE **TAGGED AND NOT LABELED** INDICATING CURRENT CERTIFIED INSPECTION NO EARLIER THAN ONE MONTH PRIOR TO SUBSTANTIAL COMPLETION.
- B. EXTINGUISHERS SHALL BE INSTALLED WITH HANDLE 4 FEET MAXIMUM FROM FLOOR.
- C. EXTINGUISHERS SHALL BE MOUNTED IN SEMI-RECESSED FULL GLASS CABINET SIZED TO MATCH EXTINGUISHERS. GLASS ON DOOR TO CABINET SHALL BE CLEAR ACRYLIC. EXTINGUISHERS IN ELECTRICAL OR OTHER EQUIPMENT ROOMS SHALL BE MOUNTED ON HOOKS WITH NO CABINET.

END OF SECTION